

Water Supplies Department

香港灣仔告士打道七號入境事務大樓 Immigration Tower, 7 Gloucester Road, Hong Kong.

電子郵遞 wsdinfo@wsd.gov.hk

e-mail

電 Telephone 2829 4367 圖文傳真

Facsimile

2824 0578

Reference (92) in WSD/K/3307/6/83

27 June 2008

Distribution: To all Licensed Plumbers and Authorised Persons

Dear Sirs,

WSD Circular Letter No. 1/2008 Amendment to Point Penalty System for **Defects in Plumbing Works Carried Out by Licensed Plumbers**

Commencing on 10 July 2008, the following changes will come into effect.

Description of three items in WWO 1008 will be amended/added as below:-

| <u>Item</u> | Section | | Current Description | Revised Description | Penalty Point |
|-------------|---|---|---|--|---------------|
| (i) | Meter Position/Check Meter Position | | | meter room / box not located at the hoarding recess area of the construction site | 3 |
| (ii) | Others |) | Syphonic type flushing cistern not provided | Approved type flushing apparatus not provided | 3 |
| | |) | plumbing arrangement not as approved | plumbing arrangement not as approved on Drawing No(s): with respect to: □ alignment □ size □ number of installation □ substantial change in installation location | 3*/5 |
| | | | | □ naming of location (3marks) □ others as stated: | |
| (iii) | Footnote | | | * Deduct 3 marks for "Naming of location" and 5 marks for all others. | |

A copy of the revised WWO 1008 is attached for your reference.

Should you have any queries, please contact our Engineer Mr. Philip AU at Tel: No. 2829 4453.

Yours faithfully,

(CHIN Chu Sum) for Water Authority

(with Chinese translation)

cc Housing Department

Buildings Department

Architectural Services Department

Fire Services Department

The Hong Kong Housing Society

The Hong Kong Institute of Architects

The Hong Kong Institution of Engineers

The Hong Kong Institute of Surveyors

Hong Kong Federation of Plumbing & Drainage Ltd.

The Institute of Plumbing and Heating Engineering – Hong Kong Council

Hong Kong Plumbing and Sanitary Ware Trade Association Ltd.

Hong Kong Licensed Plumbers Association Ltd.

Hong Kong Plumbing General Union

Hong Kong Water Works Professionals Association Ltd.

The Hong Kong Institution of Plumbing and Drainage Ltd.

The Association of Registered Fire Service Installation Contractors

of Hong Kong Limited.

Real Estate Development Association

WSD 3318/15/81 Pt. 2

| | | | 消防 | 食水 | 鹹水 | 扣分 | 備註 |
|-------------------|--|------------------|---|--|--|--|--|
| | | | Fire service | Fresh water | Salt | Penalty point | Remarks |
| Connection 總 喉 | laid to wrong position | 位置不當 | | 417-4842-0-000000-00-0000 | ****************** | 12 | |
| | not exposed | 未有外露 | | | | 1 2 | - |
| | undersized/oversized | 太小太大 | } | - | - | 2 | · |
| | no temporary connection as required | 未依規定設臨時供水喉叁 | | | | 2 | 1 |
| | sub-standard | 不合標準 | | | <u> </u> | 5 | <u> </u> |
| Piping 水 喉 | no stopcocks at appliances & branches | 支喉未裝有水掣 | <u> </u> | | | $\frac{1}{2}$ | 1 |
| | not bitumen painted & hessian wrapped | 未塗上瀝青及纏上麻布 | ļ | | | 2 | <u> </u> |
| | excessive elbows used | 使用太多曲尺喉 | | | | 1 | |
| | Concealed prior to inspection | 在視察前將藏牆喉掩蓋 | <u> </u> | - | - | 5 | |
| | not securely fixed | 安裝不穩固 | | | | 1 | |
| | of material not suitable | 喉料不適當 | | | | 3 | |
| Meter | not properly provided/indicated | 錶位不適當/沒有明確指示 | | | - | 4/1 | |
| Position/ | meter room / box not located at the hoarding recess | 建築地盤錶房或錶箱不設在圍板凹 | | | | 3 | |
| Check | area of the construction site | 處 | S. C. | | Siryon tamasian | - | |
| Meter | no loose jumper stopcock at inlet | 入水處缺少皮心掣 | | | | 3 | |
| Position | too close to wall | 太接近牆身 | <u> </u> | | - | 1 | 1 |
| 錶 位 | no non-return value | 缺少逆止閘掣 | | | | 1 | |
| | no gate value | 缺閘掣 | | | - | 1 | - |
| | of material not acceptable | 材料不合規格 | ļ | | - | 3 | |
| | no control value at inlet/outlet | 入水/出水處缺少水掣 | | | - | 2 | ***************** |
| | no washout provided | 缺少水箱去水喉 | | | | 2 | <u> </u> |
| | no overflow provided | 缺少滿溢喉 | | | <u> </u> | 3 | <u> </u> |
| | overflow undersized | 滿溢喉太少 | | | | 2 | |
| | overflow above inlet | 滿溢喉高過入水喉 | | <u> </u> | | 2 | - |
| | overflow does not discharge | 滿溢喉未有引至明顯地方 | | | | 1 | |
| Storage | into conspicuous position | | | | | 3 | |
| Tanks 儲水箱 | tank not accessible | 缺乏視察通道 | | | | 1 | - |
| | tank not provided with | | | | The state of the s | | |
| | closed-fitting covers | 缺乏緊密箱蓋 | | | disololis | 2 | |
| | storage excessive | 容量過大 | | | | 1 | |
| | no gap between potable & | 食水箱與非食水箱間 | | | | | |
| | non-potable tanks | 缺乏適當隔離 | | | | 3 | |
| | inlet incorrectly laid/sized | 入水喉位置/尺寸不當 | | | | 1 | |
| | outlet incorrectly laid/sized | 出水喉位置/尺寸不當 | | | | 1 | |
| Others 其他 | sanitary fittings incomplete | 潔具未安裝完備 | | | | 2 | |
| | plumbing incomplete | 水喉工程未安裝完備 | | | | 5 | |
| | approved type flushing apparatus not | | | | *************************************** | | |
| | provided | 未安裝已認可的沖廁設備 | | - | - | 3 | |
| | heater not properly installed | 熱水器未有安裝妥當 | | | | 2 | - |
| | no proper meter box provided | 缺乏適當水錶箱 | | <u> </u> | | 1 | - |
| | no locking device for tap | 龍頭未上鎖 | | - | | 1 | ļ |
| | plumbing arrangement not as approved on Drawing No(s): | 於圖則編號: | | on the state of th | and the second s | 3 /5 | Address of the Control of the Contro |
| | with respect to: alignment | 關於: □ 喉管路線 | | | - | *** | |
| | □ size | 口尺寸 | | | - Orași de Paris de P | 971100011111 | |
| | □ number of installation | 口 裝置數目 | | | disal description | | *************************************** |
| | □ substantial change in installation location | □ 裝置位置大幅改變 | | acceptance of the second of th | And the second of the second o | BENTLUFFFTTORROOMS | |
| | naming of location (3marks) | 口位置名稱(扣3分) | | | and the part of th | VIA PERSONAL STATE OF THE STATE | |
| | others as stated: | □ 其他列明如下: | | | - | | İ |
| | fittings and pipes not as reported | 水喉配件及水喉與「Ga」款表格附 | | | - | 1 | * |