

# 水務監督辦事處

香港禮頓道七十七號禮頓中心十三樓

電話：5-7900396

檔號：(I) in WWO (K) 6/3307/83 T.J. (1)

## 持牌水喉匠在進行喉管工程時出錯而採取之罰分制度

敬啟者：

查在現行制度下，持牌水喉匠牌照得按年更換，條件為水喉匠在過去一年內需有良好之工作表現。根據水務規例第三十七條之規定，倘水喉匠之表現未符理想，發牌當局可撤銷/暫時吊銷該水喉匠之牌照。

現時之做法為遇有持牌水喉匠負責之工程有所出錯及未符合規格時，本處即發出一標準公函(WWO 1008)，通知其將工程修正；但遇有嚴重低水準之工程時，則有遭暫時吊銷牌照之虞。

為緊密監察持牌水喉匠之工作表現，本處現決定儘快推行一項罰分制度。茲擬由一九八四年十月一日起開始試辦是項模擬之罰分制度。試行六個月後，重行檢討，期望可以在一年後正式實行。與此同時，倘對下開之建議有任何意見，請逕向港九水喉潔具業商會有限公司提出。本處現請求該會在試辦期間向本處提供其所綜合得之意見，藉作參考。

在新制度下，WWO 1008中所述之各項常犯喉管工程錯誤將按其嚴重程度分別配以不同之罰分。茲將新之罰分模式開列於函附之WWO 1008修訂本上。當水務處職員進行接收檢查時，倘發現喉管工程有任何毛病，則會記錄於修訂之WWO 1008款中之有關項目上。至於遭扣罰之分數亦會詳載其上。每次檢查完畢後，本處即會將一份經批註之WWO 1008修訂本連同罰分計算表寄交有關之水喉匠，以供參照。

根據下開情況，遇有需要時本處得發出警告信予有關之水喉匠：-

(甲) 在一次檢查中，遭扣罰之總分數超逾十分；或

(乙) 在十二個月內進行之全部安裝工程，每次檢查平均遭扣罰逾八分者。〔(甲)項事例所扣罰者為個別情況，不再包括在平均罰分內計算。〕

在十二個月內遭發警告信兩次之持牌水喉匠會導致其牌照遭暫時吊銷之處，吊銷期由發牌當局根據水務規例第三十七條(二)款之規定而裁定。

水喉匠在遭暫時吊銷牌照期間，只可繼續及完成在吊銷牌照日期前用水務表格「G」款而呈報及已獲水務監督批准之工程；但在該日期後為其他新工程而呈遞之「G」款表格，或水務監督已收訖之「G」款表格均不會受理。本處會用書面通知水喉匠關於暫時吊銷牌照事，至暫時吊銷牌照期行將屆滿時，本處亦會以書面通知該水喉匠。

查是項罰分制度無論在何種情況下，均不會妨礙發牌當局運用水務規例第三十七條(一)款所賦予之權力，在有所需要時撤銷/暫時吊銷水喉匠之牌照。敬希垂注。

此致

各持牌水喉匠  
港九水喉潔具業商會有限公司

水務監督謹啓  
(楊安正代行)

一九八四年八月二十四日

			F.S.	Fresh	Salt	Penalty Points	Remarks*
			消防	食水	鹹水	罰分	說明
Connections 總喉	Laid to wrong position	位置不當				2	
	not exposed	未有外露				2	
	undersized/oversized	太小/太大				2	
	no temporary connection as required	未依規定設臨時供水喉				2	
Piping	sub-standard	不合標準				5	
	no stopcocks at appliances & branches	支喉未裝有水掣				2	
	not bitumen painted & hession wrapped	未塗上瀝青及纏上麻布				2	
屋內喉	excessive elbow bends used	使用太多曲尺喉				1	
	backfilled & covered underground prior to inspection	在視察前將內喉掩蓋				5	
Meter Position/ Check Meter Position 錶位	not securely fixed	安裝不穩固				1	
	of material not acceptable	喉料不合規格				3	
	not properly provided /indicated	錶位不適當/沒有明確指示				4	
	no loose jumper stopcock at inlet	入水處缺少皮心掣				3	
Storage Tanks 儲水箱	too close to wall	太接近牆身				1	
	no non-return valve	缺少逆止閘掣				1	
	no gate valve	缺閘掣				1	
	of material not acceptable	材料不合規格				3	
	no control valve at inlet/outlet	入水/出水處缺少水掣				2	
	no washout provided	缺少水箱去水喉				2	
	no overflow provided	缺少滿溢喉				3	
	overflow undersized	滿溢喉太小				2	
	overflow above inlet	滿溢喉高過入水喉				2	
	overflow does not discharge into conspicuous position	滿溢喉未有引至明顯地方				3	
Others 其他	tank not accessible	缺乏視察通道				2	
	tank not provided with close-fitting cover	缺乏緊密箱蓋				2	
	storage excessive	容量過大				1	
	no gap between potable & non-potable tanks	食水箱與非食水箱間缺乏適當隔離				3	
Others 其他	inlet incorrectly laid/sized	入水喉位置/尺寸不當				1	
	outlet incorrectly laid/sized	出水喉位置/尺寸不當				1	
	sanitary fittings incomplete	潔具未安裝完備				2	
	plumbing incomplete	水喉工程未安裝完備				5	
	syphonic type flushing cistern not provided	未安裝虹吸沖廁水箱				3	
	heaters not properly installed	熱水器未有安裝妥當				2	
	no steel meter box provided	缺乏鋼掣水錶箱				1	
	no locking device for cleansing tap	清洗用水龍頭未上鎖				1	
plumbing arrangement not as approved	水喉工程規格未依批准安裝				5		

\* Remarks are given on separate sheet under same reference code.  
請參閱附頁之分項說明

File Ref. :

WWO 1008/M  
(Revised)  
(修訂本)

OFFICE OF THE WATER AUTHORITY  
ARGYLE STREET DEPOT  
KOWLOON

Dear Sir,

申請書編號 \_\_\_\_\_  
樓宇地址 \_\_\_\_\_

Application No. \_\_\_\_\_  
Premises \_\_\_\_\_

敬啟者：

The plumbing work at the above premises has been inspected and the defects marked with (X) at the reverse side of this sheet.

查上址之水喉安裝工程業經本處查驗，其中未符合規格之處已分別用(X)符號註於本函背頁之表格。

You should instruct your plumber to correct the defects. When this has been done please inform this office and a further inspection will be arranged.

茲請着令水喉匠將不合規格之項目修妥。嗣修改工程完竣後，請即知會本處，俾派員前往覆驗。

A connection will only be given when all the defects have been rectified to the satisfaction of this office.

經覆驗合格後，本處始能為上址駁喉供水。

此致

先生  
女士

Yours faithfully,

水務監督謹啟  
(\_\_\_\_\_) (代行)

for Water Authority

水務監督辦事處  
九龍亞皆老街廠

c. c. L/P's File  
Responsible L/P

一九七八年 月 日