

WIRELESS AMI SYSTEM INSTALLATION AT WATERLOO GARDEN (PROJECT NO. 123)




| SUMMARY OF INSTALLATION | | | | |
|-------------------------|-------------------------------|------|------|-------|
| LOCATION | NO. OF SMART METERS CONNECTED | | | |
| | DN15 | DN25 | DN80 | DN150 |
| BLOCK 1 | 248 | _ | 1 | _ |
| BLOCK 2 | 72 | 4 | 1 | _ |
| PLAYGROUND | _ | _ | _ | 2 |
| TOTAL | 320 | 4 | 2 | 2 |



$(((\iota_{\sqrt{\lambda}})))$ AMI MASTER STATION AMI SERVERS AT WSD > 4G CELLULAR INTERNET MODEM

BLOCK 1 BLOCK 2



F13 WATER METER ROOM G/F FLOW FLOW F13 F13 CONVERTER CONVERTER DN80 CHECK METER CHECK METER (BATTERY POWERED) (BATTERY POWERED) CHECK METER ROOM CHECK METER ROOM |

NOTES:

- 1. EACH INDOOR METER INSTALLATION LOCATION SHALL BE PROVIDED WITH ONE IP54 13A FUSED SPUR UNIT SUPPLIED BY DEDICATED MCB FOR USE BY THE WSD.
- 2. IF 13A FUSED SPUR UNIT(S) HAS BEEN PROVIDED FOR THE ELECTRO-MAGNETIC TYPE WATER METER(S), THE REQUIREMENT AT NOTE 1 CAN BE EXEMPTED.
- 3. ALL METER INSTALLATION LOCATIONS SHALL HAVE 4G SIGNAL WITH RSRP ≥ -105 dBm.
- 4. ALL WATER METERS WILL BE SUPPLIED BY WSD FOR INSTALLATION BY THE CONTRACTOR.
- 5. THIS DRAWING IS FOR DESIGN REFERENCE ONLY.

圖則名稱 drawing title REFERENCE DESIGN -SCHEMATIC DIAGRAM OF WIRELESS ADVANCED METERING INFRASTRUCTURE (AMI) SYSTEM INSTALLATION FOR PREMISES WITH MULTI-STOREY BUILDINGS

__ 核對 checked H.K. YEUNG TM/TD(2)日期 date 10/2025 比例 scale NOT APPLICABLE

圖則編號 drawing no.

W 88800/0010

編號日期 簽署 no. date initial description REVISION 辦事處 office 數字水務辦公室 DIGITAL WATER OFFICE

EQP


ROOF

ELV ROOM

WATER METER ROOMS

1/F TO 8/F

9/F



WATER METER ROOM

(SAME AS G/F)